

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Alpena Located In _____ Corner Code # _____
 (County)

1. Public Land Survey	T	<u>30N</u>	R	<u>6E</u>	<u>G-13</u>
	T	<u>30N</u>	R	<u>6E</u>	<u>H-13</u>
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on November 26, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-13 G.L.O. Lewis Clason D.S. 1840
 Set post corner section 33 and 34
 Wit: White Birch 13 N23°E 38 links
 White Birch 10 72°W 22 links

H-13 G.L.O. Lewis Clason D.S. 1840
 Set quarter section post
 Wit: Aspen 4 N20°E 23 links
 S. Maple 4 N55°W 7 links

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

G-13 Re-established the Southeast corner of section 33, 70 links (46.2') West of G-1 T.29N. - R.6E., this position fits the existing road alignment along the south line of section 33 better than a single proportion method of re-establishment.

H-13 Found a large spike fitting J.W. McNeil's distance East, set 5/8" X 32" rered with P.S. cap #33981

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 Set 5/8" X 32" rered with P.S. cap #33981
 Wit: 10" Spruce N30°E 46.32'
 14" Basswood N25°W 58.87'
 18" Oak S46°W 80.92'
 Fence corner post S30°E 40.63'
 Carsonite Post North 33'±

H-13 Set 5/8" X 32" rered with P.S. cap #33981
 Wit: 24" Oak N35°W 72.98'
 12" Red Pine N64°E 76.93'
 14" Oak S09°E 53.57'
 Power Pole S44°W 39.12'

Signed by: _____

Carl T. Kiiskila

Date: _____

10-29-02

Surveyor's Michigan License No.: 33981

