Alpena County Remonu	mentation LIBER $2_{ t PAGE}$ 30	OU3325ALPENA COUNTY MI.
	LAND CORNER RECORDATION CERTIFICATI	E MI GOOM I WI
	Filing Requirement of Act 74, Mich. P.A. 1970	
For corners in	, mild tredeficition of Not 1-3, months and 1010	" JUN 17 10 58 AM 196
Alpena	Located In: Corner Code ##	JUN 17 10 58 AM '96 * Fathyron Interest REGISTER OF DEEDS
(County)		Mathy Milly task
Public Land Survey	T 30N R 07E	REGISTER OF DEED
1. I done Land Ourvey	T 30N R 06E H1	THE OF DEEDS
	T R	
	T R	
	<u>T</u> R	
in Section S _	T	
3. Miscellaneous S _ Property in Sec. S _	T R Re	egister of Deeds Stamp & File Number
Froperty in Sec. 5 _		
4. Lot No, Record	ed Plat	
5. Private Claims		· · filliiiiiiiiiiiiiiiiiiiiiiiiiiiiiiii
		2 - 6 - 5 - 4 - 3 - 2 - 1 - 1
		3 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
t , in a	field survey on April 10 19 96	4 7 1 8 4 9 1 10 1 1 1 1 2
t,, in a	field survey on, 19, ents of P.A. 74, Michigan P.A. of 1970, the corner points mentioned	5
in lines 1 and 2 above were in confo	rmance with regulations and rules therefore as required in the	6 - 18 - 17 - 16 - 15 - 14 - 13 -
current manual of survey instructions	of the United States Department of the Interior, Bureau of Land	7
Management or by a decree of a Court shove were in conformance with the r	of Law and/or that the corner points mentioned in lines 3, 4 and 5 ules of the Michigan Board of Land Surveyors or by a Decree of a	8 19 20 21 22 23 24
Court of Law; established, re-estal	olished, monumented, re-monumented, recovered, found as	9
expressed below:		10 30 29 28 27 26 25
	, all in the same town and range, may be recorded	11
on this certificate.		12 31 32 33 34 35 36
A Description of original monut	nent and accessories and/or subsequent restoration:	13
1839: Lewis Glason	Set corner. Witnesses given: W. Birch 12 S 31 W 15, Her	■ 20 S 60° W 35
1885: W. Mirre	Set 3" square cedar stake with a piece of saw, a piece of	stove, small stones and crockey.
1904: J. McNeil	Set cedar stake. No witnesses given.	
1910: J. McNeil	Used corner. No witnesses given.	
1990: Earl T. Lewis, P.S.	Used corner. Found 1/2" rerod. Witnesses given: S 05 W	48.20' Telephone Pole, S 20 W 59.00'
	Power Pole Post, N 49 W 37.37' Power Pole. Used corner. Found 1/2" rerod. Witnesses given: N W 66	: OE! Car Pance Doct S W 60 00! Dower
Unknown: Alpena Co. Road Comm.	Pole	5.65 COL. PERCE POSC, 5 W 00.00 TOWEL
	LOTE	
	ce found and/or method applied in restoring or reestablishing	ng corner:
1996:	Found 1/2" rerod with cap #22435.	
•		
ALCONOMICS DESCRIPTION	♥.	
SURVEY	-m a-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1	TO A STATEMENT COLINTY
BENONUMEN.	1 William	P.A. 345 ALPENA COUNTY
	PE	ER APPROVED 5/5/94 Och B. Cur
JUL 2 3 19	96	1. DB Cun
	, , , , , , , , , , , , , , , , , , ,	ya .
COMMISS	SION	
	·	·
	corner and accessories established to perpetuate locating	the position of the corner:
1996:	Replaced 1/2" rerod with 1/2" x 24" rerod and place	ed appropriately stamped Alpena County
-	Remonumentation 3" aluminum cap on new 1/2" rerod in monu	ment box.
	Witnesses given:	HANGE OF MICHIGAN
	S 05° W 48.05' Power Pole	
	S 30° W 60.04' Power Pole	* EARLT. * 1
	S 70° W 102.75′ 10" Ash	PROFESSIONAL SURVEYOR
	N 40° W 45.15′ 7" Spruce	No. 1

27452 Surveyor's Michigan License No. _ FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983

PROFESSIONAL SURVEYOR No. 27452

27452 STATE