

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUN 17 10 58 AM '96

Kathy M. Ptasch
REGISTER OF DEEDS

For corners in

Alpena (County)

Located In:

Corner Code #

Table with 3 columns: Item description, Township/Range, and Corner Code. Includes items like 'Public Land Survey' and 'Property Controlling in Section'.

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13, used for recording corner locations.

I, Earl T. Lewis, in a field survey on April 10, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: Lewis Glason Set corner. Witnesses given: Cedar 14 S 40' W 18, Cedar 10 N 62' W 35
1885: W. Mirre Set 3" square cedar stake with a piece of stove pipe and some small stones.
1978: D. R. MacNeill Used corner. Found 1/2" rerod. Witnesses given: S 85' W 32.83' Power Pole, Due East 32.59' Fence Post, S 40' E 86.05' Fence Post
1985: Earl T. Lewis, P.S. Used corner. Found 1/2" rod. Witnesses given: West 32.8' Power Pole, S 40' E 86.4' Fence Post
1992: David Guthrie, P.S. Used corner. Found 1/2" rod. Witnesses given: S 86' W 32.73' Utility Pole, S 60' E 82.60' N.W. Cor. Brick Sign Base, S 20' E 86.94' Fence Post, N 20' W 60.30' Fence Post
Unknown: Alpena Co. Road Comm. Used corner. Found 1/2" rod. Wit. given: West 32.81' P. Pole, S 70' E 87.10' Fence Corner
1995: Gary St. Charles Recorded corner in Liber 2 of Corners, pg. 13. Found 1/2" rebar. Wit. given: N 88' W 44.90' Tag on Power Pole, S 70' E 100.45' Tag on Fence Post, No other witnesses available.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found 1/2" rerod.

SURVEY & REMONUMENTATION

JUL 23 1996

COMMISSION

P.A. 345 ALPENA COUNTY
PEER APPROVED 5/5/96
D.R. Co

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on existing 1/2" rerod in monument box.

- Witnesses given:
S 08' W 346.34' Power Pole
S 56' E 82.53' N.W. Corner of Sign Base
S 87' W 45.09' Power Pole (found tag)
S 33' E 100.44' Fence Post (found tag)
S 73' E 269.49' Power Service Pole



Signed by Earl T. Lewis Date June 12, 1996

Surveyor's Michigan License No. 27452