

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUN 17 10 59 AM '96

Kathy A. Matash
REGISTER OF DEEDS

For corners in Alpena (County)

Located In: Corner Code #

Table with 3 columns: Description (Public Land Survey, Property Controlling in Section, etc.), Located In (T, S, R), and Corner Code # (A6, H6, etc.).

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, Earl T. Lewis, in a field survey on May 11, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: Lewis Glason Set corner. Witnesses given: Hem 16 S 26' W 37, Hem 16 N 56' W 42
1885: W. Mirre Set 3-1/2" square cedar stake with a piece from a plough, a horse shoe, & small stones.
1901: J. McNeil Used corner. Set new cedar stake in road bed. No witnesses given.
1914: J. McNeil Set new stake in place of old one in road. No witnesses given.
1993: E.T. Lewis, P.S. Found a nail. Wit. given: N75°W 43.4' Gate Post, S45°W 47.2' P. P., S45°E 45.6' P. P., East 34.2' 4" Apple
1995: T.L. Fabis, P.S. Used and recorded corner in Liber 1 of Corners, pg. 356. Found 3/4" pipe. Witnesses given: S 82° E 34.11' 4" Apple, S 48° E 45.49' Anchor Pole, S 50° W 47.21' Power Pole, N 66° W 43.39' Post
1995: G. St. Charles Recorded corner in Liber 2 of Corners, pg. 12. Found 1/2" rebar. Wit. given: S82°E 51.80' Tag on Fence Post, S52°E 56.35' Tag on Anchor Pole, N60°W 43.50' Tag on Fence Post, S54°W 136.75' N.E. Corner of House
Unknown: Alpena Rd Comm Fd. 3/8" rerod. Wit. given: N 60° W 43.50' Fence Post, S 49° W 47.25' P. Pole, S 45° E 45.65' Anchor Post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found 3/4" pipe reset by Tom Fabis, P.S., May 10, 1996.

SURVEY & REMONUMENTATION

JUL 23 1996

COMMISSION

P.A. 345 ALPENA COUNTY
PEER APPROVED 5/15/96
D.J.B. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on 1/2" rerod in existing pipe in monument box.

Witnesses given:

- East 51.90' Fence Post (found tag)
S 52° E 56.00' Anchor Post (found tag)
S 60° W 56.52' Power Pole
S 70° W 103.71' 14" Apple



Signed by Earl T. Lewis

Date June 12, 1996

Surveyor's Michigan License No. 27452