

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUN 17 10 59 AM '96

Kathryn M. Matush
REGISTER OF DEEDS

For corners in Alpena (County)

Located In: Corner Code #

Table with 3 columns: Description, Located In (T, R, S), and Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 in a grid pattern.

I, Earl T. Lewis, in a field survey on April 10, 1996

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: Lewis Glason Set corner. Witnesses given: Hem 22 S 37' W 53, Cedar 20 N 38' W 19
1885: W. Mirre Set 4" sq cedar stake with a piece of lamp, an iron ring from a stove & some stones.
1905: J. McNeil Found old stake. Set new cedar stake. No witnesses given.
1914: J. McNeil Found old stake. Set new cedar stake. No witnesses given.
1991: T.L. Fabis, P.S. Set 1/2" rod ovr ex 1" pipe. Wit.: E 47.26' 4" Cedar, N50'E 78.44' 3" Cedar, N62'W 36.15' 6" Elm, W 33.25' Fe.P.
1993: E.T. Lewis, P.S. Fd 1/2" rod. Wit. given: N85'E 28.0' 5" Poplar, N35'E 42.4' 7" Poplar, N80'W 36.0' 6" Elm, West 33.0' 1/2" rod
1995: T.L. Fabis, P.S. Fd 1/2" rod. Wit. given: East 47.26' 4" Cedar, N50'E 78.44' 3" Cedar, West 74.91' Apple, West 33.00' Prop. Cor.
1995: G. St. Charles Recorded corner in Liber 2 of Corners, pg. 12. Found 1/2" rebar. Witnesses given: N 39' E 110.50' Tag on 16" Cedar, S 85' E 46.95' Tag on 4" Cedar, West 74.83' Tag on 3" Apple
Unknown: Alpena Rd Comm Fd 3/8" rod. Wit. given: N39'E 110.50' Tag on 16" Cedar, S85'E 46.95' Tag on 4" Cedar, West 74.83' Tag on 3" Appl

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found 1/2" rerod.

SURVEY & REMONUMENTATION

JUL 23 1996

COMMISSION

P.A. 348 ALPENA COUNTY
PEER APPROVED 5/5/96
D.T.B. Cur

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on existing 1/2" rerod in monument box.

- Witnesses given:
East 46.93' 4" Cedar
West 50.00' Property Corner
West 44.82' Power Pole
N 40' E 110.55' 18" Cedar
S 45' W 79.95' Fence Post



Signed by Earl T. Lewis

Date June 12, 1996

Surveyor's Michigan License No. 27452