

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUN 17 10 58 AM '96

Kathy M. Ptasch REGISTER OF DEEDS

For corners in Alpena (County)

Located In: Corner Code #

- 1. Public Land Survey T 30N R 07E B1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13 containing numbers 1-36.

I, Earl T. Lewis in a field survey on May 11, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Corner not set by GLO.
1910: J. McNeil Set corner in road bed. No witnesses given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1996: Set 1/2" x 18" roerod in monument box in centerline of Herron Road and in line with old fence to the South. Found nail in asphalt 1" South of road centerline and 4.5' East of set roerod.

SURVEY & REMONUMENTATION

JUL 23 1996

COMMISSION

P.A. 345 ALPENA COUNTY PEER APPROVED 5/16/96

Signature of Earl T. Lewis

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1996: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on set 1/2" x 18" roerod in monument box.

- Witnesses given:
S 10° E 33.40' Power Pole
South 127.70' 6" Apple
N 45° E 99.95' Fence Corner
N 50° W 63.10' Telephone Riser



Signed by Earl T. Lewis Date June 12, 1996
Surveyor's Michigan License No. 27452