

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

JUN 17 10 58 AM '96

Kathy J. Petash REGISTER OF DEEDS

For corners in

Alpena

(County)

Located In:

Corner Code #

1. Public Land Survey	T 30N R 07E	B5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat  
5. Private Claims

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Earl T. Lewis, in a field survey on April 10, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: Lewis Glason Set corner. Witnesses given: Tam 11 N 44' E 44, Tam 10 S 73' W 26
- 1888: W. Leroy Established corner from GLO witness trees. No monumentation given. Witnesses given: Balsam Stump 10 N 4' E 54-1/2, Black Ash 5 S 32-1/2' W 55-3/4
- 1914: J. McNeil Set new stake from witnesses from W. Leroy. No witnesses given.
- 1992: David B. Guthrie, P.S. Used corner. Set 1/2" iron rod. Witnesses given: South Fence Post 33.45', S 35' E 12" Aspen 39.63', N 15' E Fence Post 33.13', N 42' E Fence Post 40.72'.
- 1993: Earl T. Lewis, P.S. Used corner. Found 1/2" rod with cap. No witnesses given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found 1/2" rered with unidentifiable cap, 4' South of the centerline of Napper Road.

SURVEY & REMONUMENTATION

JUL 23 1996

COMMISSION

P.A. 345 ALPENA COUNTY  
PEER APPROVED 5/5/96  
Earl T. Lewis

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on existing 1/2" rered, 0.4' below surface, 4' South of the centerline of Napper Road.

Witnesses given:

- S 35' E 39.48' 14" Aspen (found nail w/cap #22435)
- N 42' E 40.65' Fence Post (found nail w/cap #22435)
- South 33.45' Fence Post (found nail w/cap #22435)
- N 15' W 46.50' 8" Spruce (found tag in face)
- S 10' W 28.62' 7" Aspen



Signed by Earl T. Lewis

Date June 12, 1996

Surveyor's Michigan License No. 27452