

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

JUN 17 10 58 AM '96

Kathy M. Ptasch REGISTER OF DEEDS

For corners in

Table with columns: Alpena (County), Located In: (Town/Range), Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, Earl T. Lewis, in a field survey on April 10, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: Lewis Glason Used Beech 14" for section corner. No witnesses given.
1891: Fred A. Rice Used corner. No monumentation or witnesses given.
1910: J. McNeil Used corner. Set new cedar stake in place of old one. No witnesses given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Set 1/2" x 18" rerod, 0.4' below surface, on line between A13 and C13, T31N-R7E, 7' South of the centerline of Taylor Hawks Road and in line with the centerline of Donnan Road to the South.

SURVEY & REMONUMENTATION

JUL 23 1996

COMMISSION

P.A. 345 ALPENA COUNTY PEER APPROVED 5/5/96

Handwritten signature

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on set 1/2" x 18" rerod, 0.4' below surface.

- Witnesses given:
N 45° W 47.10' Guy Pole
S 45° W 40.85' Power Pole
S 75° E 226.51' Power Pole
S 60° W 296.10' N.E. Corner of Building



Signed by Earl T. Lewis

Date June 12, 1996

Surveyor's Michigan License No. 27452