

SURVEY & REMONUMENTATION

JAN 25 2001

2000 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
L-2 P-315

For corners in
Alpena
(County)

Located In: Corner Code #

Barcode
Kathy J. Matash, Register Alpena Co., MI LDC 9.00
08/14/2000 10:20A
Page: 1 of 1

- 1. Public Land Survey T 30NR 07E E-7
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Wayne T. Lewis, in a field survey on 2-24-00, XX do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1839: Lewis Clason set post and witnessed.
 - 1888: W. H. LeRoy re-established Corner, and witnessed.
 - 1896: Fred A. Rice used corner, no witnesses or monumentation given.
 - 1901: J. W. McNeil used corner, no monumentation or witnesses given.
 - 1979: R. S. Scott (D. B. Guthrie, P.S.) found PK nail, and witnessed.
 - 1997: Wilcox & Assoc. found pipe w/cap, 9' East of C/L, on fence to the East and Road to the West.
 - 1998: T. L. Fabis, P.S. found nail in intersection and fence to the East and witnessed.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found PK in intersection of King Settlement Road and Kowalski Road and in line w/fence to the East.

This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY
PEER APPROVED 7-12-2000
D.J.B. E

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
2000: Placed 3" Alpena County Remonumentation Cap, stamped to identify the corner, on 1/2" rerod in monument box in place of p.k. nail.

- Witnesses:
- N 85° E 28.08' 13" Maple (ex. tag #31591)
 - S 40° E 39.92' Guy Pole (ex. tag #31591)
 - S 65° W 45.62' P. Pole (ex. tag #31591)
 - N 50° W 73.98' 7" Maple (set tag #41922)
 - N 85° E 9.63' Pipe w/cap unidentifiable



Signed by [Signature]
Surveyor's Michigan License No. 41922

Date August 14, 2000