

APR 06 1995

1994 ALPENA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

007642

For corners in

Alpena <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>30N</u> R <u>7E</u>	<u>G-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED
ALPENA COUNTY MI.
LIBER Dec 29 1 PAGE 351
2 21 PM '94
Michigan A. Johnston
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, Duane R. MacNeill, in a field survey on May 23, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1839 - Cedar Post set by Thad Pattison, D.S.

1982 - Corner not established by Alpena County Road Commission Surveyor during Road Construction project.

Witnesses:

Hem 12" N41°W 31
Beech 10" S46°E 54

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1984 - D.R. MacNeill & Associates set p.k. nail at midpoint between corners G-9 & G-11

1993 - D.R. MacNeill & Associates set 5/8" square steel pin in place of p.k. nail.

No Witnesses Supplied

Witnesses:

S75°W 84.78 Steel T-Bar
Due East 73.12 6" Tamarack

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 Remonumentation Crew found 5/8" square steel pin in bituminous surface. Placed an Alpena County Aluminum Cap, appropriately stamped, secured to a 1/2" re-rod inside a new monument box.

Witnesses:

S75°W 84.78 Steel T-Bar
N25°E 149.17 P.P.
Due East 73.12 6" Tamarack
S45°E 113.48 6" Cedar

(Removed 5/8" square steel pin & replaced with 1/2" re-rod)

P.A. 345 ALPENA COUNTY
PEER APPROVED 12-15-94
Dal B. Coker

Signed by Duane R. MacNeill
Surveyor's Michigan License No. 19237

Date 12/28/94

