

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alpena</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>2</u> T <u>30N</u> R <u>7E</u>	<u>1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Carl T. Kiiskila, in a field survey on June 22, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1 - Liber 3, page 74 Plat of Dann Subdivision 1961, Thomas Beaudris, RLS #11359, placed a concrete monument while platting.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1 - Found and accepted a concrete plat monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1 - Found a concrete plat monument. Set a carsonite marker post.
 Wit: Set nail in 22" Oak S 18° E 18.68'
 Set nail in 8" White Pine S 56° W 22.54'
 Set nail in 8" Jack Pine N 30° W 22.27'
 Set nail in 4" White Pine N 55° E 15.56'
 Carsonite post North 1'

Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981



Date 8-12-99