

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>5</u> T. <u>30</u> N. S. R. <u>8</u> E. W.		<u>C-3; D-3; C-2</u>
2. PROPERTY CONTROLLING IN SECTION <u>5</u> T. <u>30</u> N. S. R. <u>8</u> E. W.		<u>10</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S. R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl R. Johnson, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on February 12, 1986, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

See Continued


- A. ~~Description of corner evidence found and/or method applied in restoring or re-establishing corner:~~
- | | |
|---|--|
| <p style="text-align: center;">D-3</p> <p>Set D.N.R. Mon. and Cedar Post</p> <p>10" Cedar N16°W 15.9'</p> <p>8" Cedar S64°E 7.1'</p> <p>12" Cedar S50°W 12.0'</p> | <p style="text-align: center;">C-2</p> <p>Set D.N.R. Mon. and Cedar Post</p> <p>9" Balsam N80°E 24.5'</p> <p>6" Maple S 9°W 51.6'</p> <p>1" Pipe w/brass cap N85°W 49.4'</p> |
|---|--|

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- C-3 Set corner at found 1 1/2" pipe in concrete set by Marcus Schaaf in a 1919 survey.
 - 10 Set by standard survey procedure for subdivision of sections.
 - D-3 Set corner at found 1 1/2" pipe in concrete set by Marcus Schaaf in a 1919 survey.
 - C-2 Set corner at found 1 1/2" pipe in concrete set by Marcus Schaaf in a 1919 survey.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- | | |
|---|---|
| <p style="text-align: center;">C-3</p> <p>Set D.N.R. Mon. and Cedar Post</p> <p>7" cedar N48°W 9.9'</p> <p>9" cedar S48°E 28.2'</p> <p>8" cedar S25°W 12.1'</p> | <p style="text-align: center;">10</p> <p>Set 5/8" bar w/cap and cedar post</p> <p>1" pipe in concrete S60°E 2.30'</p> <p>1/2" bar w/cap N84°W 24.4'</p> <p>9" cedar N20°W 14.7'</p> <p>7" cedar N78°E 42.0'</p> |
|---|---|

SIGNED BY *Carl R. Johnson*
 SURVEYOR'S MICHIGAN REGISTRATION NO. 30083

DATE 4/3/86



FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ Alpena County

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET