

ANTRIM COUNTY
MICHIGAN
RECEIVED FOR RECORD

Dec 4 2 27 PM '96

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS

For corners in

ANTRIM
(County)

Located in: Corner Code #

- | | | |
|------------------------------------|--|------------|
| 1. Public Land Survey | T <u>30N</u> R <u>8W</u> | <u>A-5</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, NEIL L. WAY, in a field survey on NOV. 4, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO SET POST AUG. 1855, BEECH 18 S64W 47
BEECH 14 S27E 56
HEM 16 N69W 10
SUGAR 14 N18E 30

CHURCH MAY 1886 USED COR
JONES #23514 FOUND 1" IRON PIPE RAISED WITH R.R SPK. & REC ICR.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RAIL ROAD SPIKE OVER 1" IRON PIPE IN CENTERLINE AT INTERSECTION OF ROAD & OCCUPATION LINE TO NORTH

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Ratified by peer group
in accordance with
P.O. 345
Antrim Co. Chairman

SET CO. MT.
S51W 39.68' P. POLE
S02E 51.20' BSWP. 16
N45W 42.70' P. POLE
N55E 41.25' P. POLE



Arthur L. Lennox
Nov. 26, 1996

Signed by _____
Surveyor's Michigan License No. 28432

Date NOVEMBER 25, 1996

113

002 349