

DEC 4 2 27 PM '96

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Wanda L. Conway  
REGISTER OF DEEDS

For corners in

ANTRIM

(County)

Located In:

Corner Code #

1. Public Land Survey

T 30N R 8W

A-7

T R

T R

T R

2. Property Controlling  
in Section

S

T R

S

T R

3. Miscellaneous  
Property in Sec.

S

T R

S

T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, NEIL L. WAY, in a field survey on NOV. 4, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO SET POST AUG. 1855 AT TOP HILL, LYNN 14 N73E 1&, SUGAR 8 S35E 25, BEECH 14 S17W 23, BEECH 14 S17W 23, BEECH 9 N26W 30  
CHURCH DEC 1885 FOUND STK & WITNESS GLO  
CHAMBERLAIN FOUND & USED 2" IRON PIPE 1980


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/2" IRON PIPE & WITNESS AT TOP OF HILL AS STATED IN GLO NOTES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Ratified by peer group  
in accordance with  
P.O. 345  
Antrim Co. Chairman

SET CO. MONUMENT  
S05W 17.70' IRONWOOD 6"  
S28E 17.30' MPL 14"  
N65E 49.46' WHITE BIRCH 12"  
S75W 6.25' IRONWOOD 3"



Arthur L. Lennox  
Nov. 26, 1996

Signed by \_\_\_\_\_  
Surveyor's Michigan License No. 28432

Date NOVEMBER 25, 1996

002 351