

ANTRIM COUNTY
MICHIGAN
RECEIVED FOR RECORD

DEC 4 2 27 PM '96

Wanda R. Conway

REGISTER OF DEEDS

SURVEY &
REMONUMENTATION

JUL 30 1999

SECTION

Register of Deeds Stamp & File Number

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ANTRIM

(County)

Located In:

Corner Code #

1. Public Land Survey

T 30N R 8W

A-8

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling
in Section

S ___

T ___ R ___

S ___

T ___ R ___

3. Miscellaneous
Property in Sec.

S ___

T ___ R ___

S ___

T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, NEIL L. WAY, in a field survey on NOV 4, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO SET POST AUG. 1855, ELM 48 S40W 17, HEMLOCK 36N27E 26
CHURCH JUNE 23, 1884 RECOVERED COR & WIT'S
CHURCH MAY 6, 1886 USED AGAIN
CHAMBERLAIN 1980 USED & RECORDED CERT. 2" IRON PIPE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 2" IRON PIPE ON CENTERLINE OF ROAD TO WEST AND ON LINE WITH OLD FENCES TO NORTH AND SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET CO. MOUNT.
S13W 54.10' MPL 4"
N15W 27.30' MPL 40"
N40E 27.25' MPL 6"
N43W 57.80' CHY 4"

Ratified by peer
group
in accordance with
P.O. 345
Antrim Co. Chairman

Arthur L. Lennox

Arthur L. Lennox
Nov. 26, 1996



Signed by _____
Surveyor's Michigan License No. 28432

Date NOVEMBER 22, 1996

LIBRY 002 348