

ANTRIM COUNTY
MICHIGAN
RECEIVED FOR RECORD

DEC 4 2 27 PM '96

Wanda R. Conway

REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

JUL 8 0 1996

SECTION
Register of Deeds Stamp & File Number

For corners in

ANTRIM
(County)

Located in:

Corner Code #

1. Public Land Survey

T 30N R 8W A-9

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, NEIL L. WAY, in a field survey on 4, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

GLO SET POST AUG. 1855, BEECH 9 S64W 43, SUGAR 14 N9W 16, BEECH 9 N10E 32, BEECH 15 S53E 28
CHURCH JUNE 1884 FOUND OLD STK & WIT'S
CHURCH MAY 1892 FOUND CEDAR FENCE POST & WIT'S
OSTLING FEB 1972 SET IRON & CAP AT CEDAR FENCE POST.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON & CAP OSTLING # 12026 AT OLD FENCE CORNER TO SOUTH & WEST & 1/2 CHAIN EAST OF CREEK AS NOTED IN GLO NOTES

Ratified by peer group
in accordance with
P.O. 345
Antrim Co. Chairman

Arthur L. Lennox

Arthur L. Lennox

C. Description of monument for corner and accessories furnished to perpetuate locating the position of the corner:

SET CO. MONT.
N73E 25.30' MPL 10
S45E 17.30' MPL 10
N65W 10.42' MPL 12" TWIN
S53W 8.93 MPL 10



Signed by _____
Surveyor's Michigan License No. 28432

Date NOVEMBER 22, 1996

002 344