

Dec 4 2 26 PM '96

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Wanda R. Conway

REGISTER OF DEEDS

For corners in

ANTRIM

(County)

Located In:

Corner Code #

1. Public Land Survey

T 30N R 9W

I-4

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling
in Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, NEIL L. WAY, in a field survey on NOV. 4, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO SET CORNER POST AUG. 1855, Y-BIRCH 10 N55E 15, Y-BIRCH 14 S60W 13
CHURCH (CO. SURVEYOR) OCTOBER 1887 & DECEMBER 1911 RECOVERED OLD CORNER & WITNESS AND SET CEDAR STAKE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1' 14" IRON PIPE AND WITNESS IN WOODS JUST WEST OF SWAMP AS STATED IN CHURCH RECORDS OF 1887

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Ratified by peer group
in accordance with
P.O. 345
Antrim Co. Chairman
Arthur L. Lennox
Arthur L. Lennox
Nov. 26, 1996

SET COUNTY MONUMENT
S70W 24.14' OAK 20
N60W 16.20' Y-BIRCH 10
S17E 30.65' OAK TWIN 20
N60E 11.22' Y-BIRCH 12



Signed by *Neil L. Way*
Surveyor's Michigan License No. 28432

Date NOVEMBER 25, 1996

104

002 340