

DEC 4 2 27 PM '96

*Wanda R. Conway*

REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ANTRIM

(County)

Located In:

Corner Code #

1. Public Land Survey

T 30N R 9W I-5

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, NEIL L. WAY, in a field survey on NOV. 4, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5									●				
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO SET CORNER POST AUG. 1855, SUGAR 12 N64E 40, HEM 8 S35W 29  
CHURCH (CO. SURVEYOR) MARCH 1909 & DEC 1911 RECOVERED OLD CORNER & WITNESS  
M. FEINDT SET CONC. MONUMENT WHILE DOING PLAT COTTRILLS GRAND TRAVERSE BAY SUB #4 IN 1959.  
A. LENNOX FEB 1995 FOUND MONUMENT & WITNESS, PREPARED LCR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 4" CONCRETE MONUMENT & WITNESS IN WOODS 33±N & 263± EAST OF NE CORNER OF COTTRILL'S #4 SUBDIVISION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:



Ratified by peer group  
in accordance with  
P.O. 345

Antrim Co. Chairman

*Arthur L. Lennox*

Arthur L. Lennox  
Nov. 26, 1996

SET COUNTY MONUMENT  
S25W 5.25' MPL 5  
S60W 16.97' OAK 12  
N05W 7.75' Y BIRCH 8  
N63E 16.35' OAK TWIN 10

Signed by *Neil L. Way*

Surveyor's Michigan License No. 28432

Date NOVEMBER 25, 1996

*106*

002 342