

ANTRIM COUNTY
MICHIGAN
RECEIVED FOR RECORD
DEC 4 2 27 PM '96
Wanda R. Omsday
REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ANTRIM (County)	Located In:	Corner Code #
1. Public Land Survey	T 30N R 9W	I-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, NEIL L. WAY, in a field survey on NOV. 4, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15	●	14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO SET CORNER POST AUG. 1855, HEM 12 N69E 22, HEM 8 S40W 42
CHURCH (CO. SURVEYOR) MARCH 1909 RECOVERED CORNER & WITNESS, SET STAKE & ADDED WITNESS
BEECH 16 N63E 9, BIRCH 18 N54 1/2W 44
A. LENNOX FEBRUARY 1995 SET 1/2" IRON & CAP AT MIDWAY ON LINE IN NORTH-SOUTH FENCE & 12'
SOUTH OF EAST-WEST FENCE WITNESS.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON & CAP #20357 & WITNESS IN NORTH-SOUTH FENCE

Ratified by peer group
in accordance with
P.O. 345
Antrim Co. Chairman
Arthur L. Lennox
Arthur L. Lennox
Nov. 26, 1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET COUNTY MONUMENT WITH
S75W 1.85' HEMLOCK 14
N25E 13.73' BEECH 38
N80E 11.90 HEMLOCK 8
S13E 21.63' HEMLOCK 6



Signed by _____
Surveyor's Michigan _____

Date NOVEMBER 25, 1996

107