

DEC 4 2 26 PM '96

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

and *B. Conway*
REGISTER OF DEEDS

For corners in

ANTRIM

Located In:

Corner Code #

(County)

1. Public Land Survey

T30N R 9W I-7

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, NEIL L. WAY, in a field survey on NOV. 4, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		13		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO SET CORNER POST AUGUST 1855 HEM 16 N45E 9, HEM 12 S65W 22
CHURCH (COUNTY SURVEYOR), NOVEMBER 1903, MARCH 1909 RECOVERED OLD CORNER & WITNESS MARKED
HEM 8 N28 1/2 W 60
HEM 10 S17E 53

A. LENNOX #20357 FOUND & WITNESS 1/2" BAR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON ROD IN CENTERLINE OF ROAD ON BRUSH LINE & IRON & CAP #25873 TO NORTH 33'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET COUNTY MONUMENT IN MONUMENT BOX
N23°W 59.95' CORNER 8"
NO5W 62.15' HLK 5"
S40W 53.20' HLK 16"
S06E 55.62' MPL 20"

Ratified by Peer Group
in accordance with
P.O. 345
Antrim Co. Chairman

Arthur L. Lennox
Arthur L. Lennox
Nov. 26, 1996



Signed by _____
Surveyor's Michigan License No. 28432

Date NOVEMBER 25, 1996

101

002 337