

DEC 4 2 27 PM '96

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Wanda R. Conway

For corners in

ANTRIM
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|--------------------------|-------|
| 1. Public Land Survey | T <u>30N</u> R <u>9W</u> | J-5 |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, NEIL L. WAY, in a field survey on NOV. 4, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5										●			
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

PLO SET POST AUG. 1855, BEECH 14 N77W 12, SUGAR 8 S81E 7
CHURCH (CO. SURVEYOR) OCT. 1887, JULY 1902, MARCH 1909, DEC 1911 RECOVERED CORNER FROM WITNESS & EVIDENCE TO SOUTH.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/4" IRON AND WITNESS IN C/L TWO TRACK ROAD E-W & ON LINE WITH OLD FENCES NORTH AND SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:



Ratified by peer group
in accordance with
P.O. 345
Antrim Co. Chairman
Arthur L. Lennox
Arthur L. Lennox
Nov. 26, 1996

SET COUNTY MONUMENT
S65°E 46.0' BSWD 14
N15°W 17.90 POP 12
S65W 23.83' MPL 6
N58W 42.02' MPL 14

Signed by *Neil L. Way*
Surveyor's Michigan License No. 28432

NOVEMBER 25, 1996
Date _____

002 353

117