

DEC 4 2 26 PM '96

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1976 *Neil L. Way*

For corners in

ANTRIM (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>30N</u> R <u>9W</u>	<u>J-7</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, NEIL L. WAY, in a field survey on NOV. 4, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO SET CORNER POST AUG. 1855, BEECH 18 N43E 27, HEMLOCK 10 S64W 22
CHURCH (CO. SURVEYOR) JULY 1902, NOVEMBER 1903, MARCH 1909 SET FLAT IRON BAR IN CENTERLINE
OF ROAD AT BRUSH LINE SOUTH FROM TESTIMONY OF NEIGHBOR

MARKED BIRCH 8 S31W 41
BIRCH 8 S26E 57

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO CORNER ROAD CUT, SET 1/2" IRON ROD & CAP #28432 AT MIDPOINT AND ON LINE BETWEEN
SW CORNER AND SE CORNER.
CORNER FALLS 2' NORTH OF CENTERLINE ROAD AND ON LINE WITH OLD FENCE LINES TO THE NORTH
AND SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET COUNTY MONUMENT IN MONUMENT BOX
N25E 35.9 POWER POLE
S47W 56.31' BASSWOOD 16"
S35E 53.40' POPLAR 12"



Ratified by peer group
in accordance with
P.O. 345
Antrim Co. Chairman

Signed by *Neil L. Way* Date NOVEMBER 25, 1996
Surveyor's Michigan License No. 28432 Lennox
NOV. 26, 1996

002 339