

DEC 4 2 27 PM '96

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Wanda R. Conway  
REGISTER OF DEEDS

For corners in

<u>ANTRIM</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>30N</u> R <u>9W</u>	K-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, NEIL WAY, in a field survey on NOV 4, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:  
GLO SET POST AUG. 1855, SUGAR 12", N50W 31, BEECH 18, S52E 64  
CHURCH (CO. SURVEYOR) MAR. 1909, DEC. 1911, FOUND STONE & KETTLE AROUND IT.  
STATE HIGHWAY PLANS SHOW COR IN C/L INT. ROADS 1952  
JONES #23514 SHOWS IRON & MON BOX C/L INT. ROADS LIB 002, PG 55, AUG 1983  
L. FIENDT 1978 CERT SHOWS SAME

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON IN MON BOX IN C/L INT ROADS THAT AGREE WITH HIGHWAY PLANS OF 1952 & WIT'S

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Ratified by peer group  
in accordance with  
P.O. 345  
Antrim Co. Chairman  
Arthur L. Lennox  
Nov. 26, 1996

SET COUNTY MONT IN MON BOX  
S65°W 63.70' MPL 18"  
N57°E 49.90' STREET SIGN  
N41°E 110.5' R. PINE 6"  
N75°E 97.70' P. POLE



Signed by \_\_\_\_\_  
Surveyor's Michigan License No. 28432

Date NOVEMBER 22, 1996

002 345

109