

ANTRIM CO. . . .  
MICHIGAN  
RECEIVED FOR RECORD  
DEC 4 2 26 PM '96

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 *Wanda R. Conway*

For corners in

ANTRIM (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>30</u> N R <u>9</u> W	<u>K-6</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

REGISTER OF DEEDS  
  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, NEIL L. WAY, in a field survey on NOV. 4, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14	●	13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO SET POST AUG. 1855, SUGAR 24 N65E 3, BEECH 8 S21W 21  
CHURCH (CO. SURVEYOR) MARCH 1909 SET BLACK BOTTLE AND STONES AROUND IT. ELM 6 N17½W 81:14 LK  
STATE HIGHWAY PLANS 1952 SHOW CORNER 1.99' WEST OF CENTERLINE INTERSECTION OF ROADS.  
L. FEINDT APRIL 1978 SET SPIKE OVER IRON  
S75W 104.3 POWER POLE  
N60W 52.00 POWER POLE  
S80W 130.9 POWER POLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON IN MONUMENT BOX 2' WEST OF CENTERLINE INTERSECTION OF ROADS AS SHOWN ON HIGHWAY PLANS OF 1952.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET COUNTY MONUMENT IN MONUMENT BOX  
S69°W 42.40' STOP SIGN  
S69°E 104.50' POWER POLE  
S73°E 89.00' HYDT  
N60°E 37.50' STREET SIGN

Ratified by peer group  
in accordance with  
P.O. 345  
Antrim Co. Chairman

*Arthur L. Lennox*

Arthur L. Lennox  
Nov. 26, 1996



Signed by \_\_\_\_\_  
Surveyor's Michigan License No. 28432

Date NOVEMBER 25 1996

002 341