

DEC 4 2 27 PM '96

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Wanda R. Conway

REGISTER OF DEEDS

For corners in

ANTRIM

(County)

Located In:

Corner Code #

1. Public Land Survey

T 30N R 9W L-7

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling in Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, NEIL L. WAY, in a field survey on NOV. 4, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO SET POST AUG. 1855, SUGAR 9 N60E 13, SUGAR 9 S15W 34 CHURCH JULY 1902, FND CEDAR STK/PUMP CYLINDER ON TOP CHAMBERLAIN AUG 1977 FOUND BOAT SPIKE USED BY CHARLEVOIX ABSTRACT SINCE 1966, REPLACED WITH "T" IRON & WIT'S

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND "T" IRON 3' SOUTH OF C/L ROAD ON OLD FENCE TO NORTH & CHAMBERLAIN WIT'S

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Ratified by peer group
in accordance with
P.O. 345
Antrim Co. Chairman

SET CO. MONT.
S45W 43.40' ELM 6"
S20°E 23.64 MPL 8"
N35E 89.55 J. PINE 8"
NORTH 33' IRON PIPE

Arthur L. Lennox
Arthur L. Lennox
Nov. 26, 1996



Signed by _____
Surveyor's Michigan License No. 28432

Date NOVEMBER 22, 1996

002 347