

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ALPENA

(County)

Located In:

Corner Code #/

1. Public Land Survey	T	31N	R	5E	H-7, H-9
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	22	T	R	6, 9
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL T. KIISKILA, in a field survey on NOVEMBER 30, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

H-7 H-9 b
 (NO EVIDENCE OF G.L.C. CORNER, B.T'S, LINE TREES OR TOPOGRAHY, AS CALLED OUT IN G.L.C. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7	H-9	b	9
REESTABLISHED THE NE 1/4 COR OF SEC. 22 MIDWAY AND ON LINE BETWEEN FOUND SECTION CORNERS 1/2 MILE TO EAST AND WEST.	FOUND 5/8" IRON IN MON BOX FOR SW 1/4 COR OF SEC. 22. COR FITS MSHD 1967 SURVEY DATA ON SOUTH LINE OF SEC. 22.	ADJUSTED THE FOUND 3/4" PIPE WITH P.S. DUANE MacNEILL #19237 CAP, N55°25'E 5.6' TO THE PROPER POSITION PER STANDARD BLM INSTRUCTIONS FOR SUBDIVISION OF A SECTION; FOR THE NE CORNER OF THE SW 1/4 OF THE NE 1/4 OF SEC 22.	ADJUSTED THE FOUND 3/4" PIPE WITH P.S. DUANE MacNEILL #19237 CAP N66°14'E 2.3' TO THE PROPER POSITION PER STANDARD BLM INSTRUCTIONS FOR SUBDIVISION OF A SECTION; FOR THE SE CORNER OF THE SW 1/4 OF THE NE 1/4 OF SEC. 22. <i>E-W fence is 10' x 2' N.</i>

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7	H-9	b	9
SET DNR MON AND CEDAR POST. 4" ASH S18°W 15.5' 5" W. BIRCH N45°W 26.9' 17" CEDAR N10°E 28.9' 4"-8" MAPLE (CLP) S74°E 31.4'	FD 5/8" IRON ROD IN MON BOX. WHITE GUARD POST S48°E 49.51' WHITE GUARD POST S18°W 58.79' RED TOP CEDAR POST (PK) N06°E 50.49' WHITE GUARD POST S55°W 41.91' CTR GRAVEL RD SOUTH, EAST 3' CTR M-32, SOUTH 1'	CAPPED 3/4" PIPE, SET CARSONITE POST. 14" MAPLE S33°W 30.95 8" TW. MAPLE S68°W 28.41' 12" MAPLE N45°W 13.69' 8" TW. CEDAR S40°E 26.07'	3/4" CAPPED PIPE, #19237. 10" ASH N65°E 20.65' 10" MAPLE N17°E 14.45' 8" BALSAM N73°W 41.43' 18" ASH S04°E 34.74'

Signed by Carl T. Kiiskila Date 1-23-96

Surveyor's Michigan License No. 33981