

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
ALPENA  
 (County)

	Located In:	Corner Code <del>##</del>
1. Public Land Survey	T <u>31W</u> R <u>SE</u>	M-7, M-8
	T _____ R _____	M-9
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, CARL T. KIISKILA, in a field survey on NOVEMBER 30, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 M-7 M-8 M-9  
 (NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES OR TOPOGRAPHY, AS CALLED OUT IN G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 M-7 M-8 M-9  
 ACCEPTED 1/2" REROD FOR THE NE COR SEC. 24. CORNER ALSO ACCEPTED BY D.GUTHRIE, P.S. #22435, IN 1995 CERT. OF SURVEY. CORNER IS IN N-S ROAD WITH FENCES TO EAST AND WEST.  
 ACCEPTED FD 1/2" BAR FOR THE E 1/4 COR. OF SEC. 24. COR FITS 1995 CERT. OF SURVEY INFO. BY D.GUTHRIE, PS #22435 AND ALSO 1892 SURVEY BY JOHN H. LEROY, CO. SURVEYOR, IN SEC 24. CENTER OF N-S ROAD IS EAST 14'. CENTER OF E-W ROAD IS SOUTH 3.5'  
 FOUND 1/2" IRON IN MON BOX FOR SE COR OF SEC. 24. COR FITS 1892 SURVEY BY JOHN H. LEROY, CO. SURVEYOR, IN SEC. 24.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 M-7 M-8 M-9  
 FOUND 1/2" REROD. #POWER POLE N85°W 29.49' #POWER POLE N40°E 64.88' #8" & 4" TW.ELM S84°E 68.84' 3" ELM S24°W 76.51' #WIT. BY D.GUTHRIE, PS #22435  
 FOUND 1/2"x 1 1/2" FLAT BAR IN ROAD INTERSECTION. 16" CMP. N.END, CHISELED "X" N47°W 36.11' 16" CMP S.END, CHISELED "X" S50°W 36.62' \*\*TELE.POLE N73°E 75.67' #WIT. BY OTHERS. \*\*WIT BY D.GUTHRIE, PS#22435  
 FD. 1/2" IRON IN MON. BOX. P.K. in GUARD RAIL POST N15°E 69.41' P.K. in GUARD RAIL POST N45°E 86.77' FENCE POST S07°W 62.95' SIGN POST S38°E 39.40' CTR. M-32 NORTH 2.5' GRAVEL RD. TO N. EAST 29'



Signed by Carl T Kiiskila Date 1-23-96  
 Surveyor's Michigan License No. 33981