

1997 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 00002 Page 0093

For corners in

<u>Alpena</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 32N R 05E	E13
	T 31N R 05E	<u>E01</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____	_____
	S _____ T _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____	_____
	S _____ T _____	_____

STATE OF MICHIGAN  
County of Alpena  
Recorded  
08-25-1997 12:01:00  
Kathy J. Natash  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Wayne T. Lewis, in a field survey on March 3, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: Butler Ives, D.S. Set post. Witnesses given: Dead Cedar 14 N 64° W 14, Dead Cedar 15 N 71° E 35.
- 1913: J. McNeil & W. Leroy Set 2" gas pipe. Set witness stake 50 links South.
- 1974: Porter Survey Fd 1/2" pipe. Wit. given: S 10° W 20.84' 20" Bam, N 35° W 71.58' 9" Tam., N 25° E 45.08' 6" Spruce.
- 1976: R.S. Scott Engineering Found 1" pipe. No witnesses given.
- 1990: Thomas L. Fabis, P.S. Set 1/2" rod 5' South of road C/L by proport. method using D-13 and F-13, referring to 1913 notes from J. W. McNeil. Recorded in Liber 1, page 222, by T. Fabis. Wit. given: S 40° E 34.88' 8" Balm of Gilead, S 28° W 55.61' 7" Aspen, N 16° E 73.35' 12" Tamarack, N 46° W 60.64' 7" Jack Pine.
- 1994: Carl T. Kiiskila, P.S. Fd 1/2" rod w/cap and recorded cor in Liber 1, page 354. Wit. given: S 37° E 34.92' 10" Balsam, S 55° W 43.93' 4" Spruce, S 80° W 76.16' 6" Tw. Spruce, North 34.02' Cedar Post, C/L road North 4.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

- 1997: Found 1/2" rerod with cap #31591.

SURVEY & REMONUMENTATION

JUL 30 1997

SECTION

P.A. 345 ALPENA COUNTY  
PEER APPROVED 6/19/97  
*D.D.B. Lee*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1997: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on existing rerod, 6" below road surface.



- Witnesses given:
- S 45° E 34.95' 12" Bam (found tag #31591 & blaze)
  - S 50° W 37.02' 3" Spruce (found nail & blaze)
  - S 80° W 76.14' 6" Spruce (found nail & blaze)
  - N 05° W 34.05' DNR Corner Marker

Signed by Wayne T. Lewis

Date August 21, 1997

Surveyor's Michigan License No. 41922