

1997 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Liber **00002** Page **0094**

<u>Alpena</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 32N R 05E T 31N R 05E T _____ R _____ T _____ R _____	G13 <u>G01</u> _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____

STATE OF MICHIGAN  
County of Alpena  
Recorded  
08-25-1997 12:01:10  
Kathy J. Matash  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Wayne T. Lewis, in a field survey on March 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: Butler Ives, D.S. Set post. Witnesses given: Dead Ash 10 N 10° W 7, Dead Ash 12 N 81° E 22.
- 1913: J. McNeil & W. Leroy Set 2" gas pipe in North edge of road bed 20 links East of large ditch or culvert. No wit. given.
- 1976: R.S. Scott Assocs. Set 1/2" rod. Witnesses given: S 35° E 53.00' 6" Elm, N 10° W 51.90' 8" Elm, N 50° E 74.20' 14" Maple.
- 1990: Thomas L. Fabis, P.S. Set 1/2" rod 10' North of road centerline by proportionate method using F-13 and H-13, referring to 1913 notes from Joseph W. McNeil. Thomas L. Fabis recorded corner in Liber 1, page 222.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1997: Found 1/2" rerod w/unidentifiable cap. Also found 1/2" rerod S 54°46'37" E 16.88' from capped rod.

SURVEY &  
REMONUMENTATION

JUL 8 0 1997

SECTION

P.A. 345 ALPENA COUNTY  
PEER APPROVED 5/1/97

*D.P.A. Lewis*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1997: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on existing rerod, 6" below road surface.



- Witnesses given:
- N 55° E 51.95' 7" Ash (found nail & tag #31591, set tag #41922)
  - N 44° W 64.67' 7" Ash (found nail & tag #31591, set tag #41922)
  - S 52° W 57.77' 6" Maple (found blaze)
  - S 40° E 77.55' 7" Ash (found blaze)
  - West 18.00' Centerline of culvert.

Signed by *Wayne T. Lewis*  
Surveyor's Michigan License No. 41922

Date August 21, 1997