

1997 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 Liber 00002 Page 0099

For corners in

Alpena Located In: Corner Code #
 (County)

1. Public Land Survey T 32N R 05E K13
 T 31N R 05E (K01)
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

STATE OF MICHIGAN
 County of Alpena
 Recorded
 08-25-1997 12:02:00
 Kathy J. Matash
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Wayne T. Lewis, in a field survey on March 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1855: Butler Ives, D.S. Set post. Witnesses given: Dead Cedar 12 N 32° W 3', Dead Cedar 8 N 61° E 15'.
 1888: William Leroy Found old corner. Set 3" square cedar stake in ditch on East side of road. No witnesses given.
 1913: J. McNeil & W. Leroy No monumentation or witnesses given.
 1976: R.S. Scott Assocs. Found 1/2" rod. Witnesses given: N 45° E 57.82' Power Pole, S 46° E 34.85' 16" Bam, East 99.33' 18" Spruce.
 Thomas L. Fabis, P.S. Found 3/4" iron rod. No witnesses given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Found 5/8" rod. Set 1/2" rerod.

SURVEY &
 REMONUMENTATION

P.A. 345 ALPENA COUNTY
 PEER APPROVED 5/1/97
D.J.H. Lee

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1997: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on set 1/2" rerod, 6" below driveway surface.



Witnesses given:
 N 85° E 18.58' Gate Post
 N 45° E 57.90' Power Pole
 S 45° E 35.05' 16" Bam Stump (found nail)
 S 43° E 49.35' 6" Aspen

Signed by Wayne T. Lewis
 Surveyor's Michigan License No. 41922

Date August 21, 1997