

NOV 16 1998

P.A. 345 ALPENA COUNTY
PEER APPROVED 8/10/98
D. T. Kibbe

1998 Alpena County Remonumentation Corner SECTION
LAND CORNER RECORDATION CERTIFICATE Liber 00002 Page 0140
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alpena</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 31N R6E	A-2 ✓
	T 31N R5E	M-2 ✓
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
County of Alpena
Recorded
08-20-1998 09:17:37
Kathy J. Matash
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel T. Kibbe, in a field survey on March 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		9		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: GLO Survey by Butler Ives-set 1/4 section post; referenced: W. Pine 30-S50W-87/W. Pine 30-N30E-75
- 1901: County Survey by Jim H. LeRoy-set reddish granite 15" x 9" w/pieces of broken crock around stone; referenced: W. Pine stump 30-S51 1/2-W87 ONBT/W. Pine stump 40-N71 3/4 E-96 NWT/Cedar Fence Post 8-S87 1/2 E 50 1/4
- 1909: County Survey by Jos. W. McNeil-ran from corner established by Jim H. Leroy
- 1920: County Survey by Jim H. Leroy-ran from established corner
- 1995: Survey by David B. Guthrie-set 1/2" iron bar; referenced: 15" Spruce-N17W-96.2'/P.Pole-N40E-69.88' 15" Spruce-S50W-52.45'/'4" Ash-S60E-75.60'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998: Remon. Survey by Daniel T. Kibbe-found 1/2" rebar. 1' West of CL North-South road. 1' South of CL road to West. 15' South of CL road to East.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1998: Placed 3" Alpena County cap stamped to identify the corner over 1/2" iron rod.
Referenced:

- Set tag over nail in 15" Spruce N10W-96.25'
- FD DBG tag in Power pole N40E-69.70'
- Set tag over nail in 15" Spruce S50W-52.45'
- FD DBG tag in 4" Ash S60E-75.62'

Signed by Daniel T. Kibbe
Surveyor's Michigan License No. 37278



Date August 14, 1998