

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

JUN 17 10 58 AM '96

Kathy A. McIntosh REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in Alpena (County)

Located In: Corner Code #

Table with 3 columns: Description, Located In (T, R, S), and Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

4. Lot No. Recorded Plat
5. Private Claims

I, Earl T. Lewis, in a field survey on April 10, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: Lewis Glason Set corner. Witnesses given: W. Pine 18 N 10° E 13
1969: J. L. Scott Used corner. No monumentation or witnesses given.
1992: Earl T. Lewis, P.S. Used corner. Found 1/2" rod. Witnesses given. N 20° E 53.85' Power Pole, N 20° W 75.70' 6" Maple.
1993: Earl T. Lewis, P.S. Used corner. Found 1/2" rod. Witnesses given. N 20° E 53.85' Power Pole, N 20° W 75.70' 6" Maple, West 131.55' Traffic Sign, S 20° W 62.30' 6" Maple.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1996: Found p.k. nail over p.k. nail in asphalt.

SURVEY & REMONUMENTATION

JUL 23 1996

COMMISSION

P.A. 345 ALPENA COUNTY

P.A. 345 ALPENA COUNTY PEER APPROVED 5/5/96

Earl T. Lewis

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1996: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on set 1/2" rered in monument box.

- Witnesses given:
N 20° W 73.30' 4" Maple
N 20° E 53.95' Power Pole
S 20° W 62.10' 6" Maple
N 10° E 257.90' Power Pole



Signed by Earl T. Lewis Date June 12, 1996

Surveyor's Michigan License No. 27452