

JUN 17 10 58 AM '96

Kathryn Mptash
REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Alpena (County) Located In: Corner Code =#

1. Public Land Survey	T 31N R 07E	A11
	T 31N R 06E	H11
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Earl T. Lewis, in a field survey on April 10, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: Butler Ives Set corner. Witnesses given: Cedar 10 S 12° W 20, Cedar 9 N 24° W 15
- 1883: W. Nirre Used corner. Set 4" sq cedar stake from GLO wit. Left brick, plough piece & stones at cor. No wit.
- 1891: Fred A. Rice Found stake. No witnesses given.
- 1914: J. McNeil Set cedar stake in place of old one. No witnesses given.
- 1961: N.C. Caldwell, P.S. Set 3/4" x 36" screw from bumper jack from witness on record at Scott Engineering Co. Witnesses given: N 76° W 49.81' Fence Post, S 52° W 60.55' Fence Post, N 49° W 37.37' Power Pole.
- 1987: David Guthrie, P.S. Used corner. Found 1/2" iron rod. Witnesses given: N 80° W 49.42' Gate Post, N 75° E 55.79' Road Sign, S 70° E 44.00' Road Sign.
- Unknown: Alpena Co. Road Comm. Used corner. Found 1/2" rerod. Witnesses given: N 45° W 56.75' Fence Post, S 50° W 51.50' Fence Post, S 45° E 43.30' Road sign.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found 1/2" rerod.

SURVEY & REMONUMENTATION

JUL 23 1996

COMMISSION

P.A. 345 ALPENA COUNTY
PEER APPROVED 5/5/96

D. B. C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on existing 1/2" rerod in monument box.

- Witnesses given:
- N 40° E 73.38' 4" Poplar
 - N 75° W 49.52' Steel Gate Post
 - S 50° W 60.80' Fence Post, Broken Off
 - N 75° E 192.92' 6" White Pine



Signed by Earl T. Lewis Date June 12, 1996
 Surveyor's Michigan License No. 27452