

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
 Alpena _____ Located In _____ Corner Code # _____
 (County)

1. Public Land Survey	T	31N	R	6E	J-8
	T	_____	R	_____	_____
2. Property Controlling in Section	S	23	T	31N	R 6E 9
	S	_____	T	_____	R _____
3. Miscellaneous Property in Section	S	_____	T	_____	R _____
	S	_____	T	_____	R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on, June 10, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-8 Pages 221 thru 224 County Survey Records March 1893
 Fred A. Rice established center of section 23.

9- Wayne T. Lewis P.S. #41922 set this corner while doing a survey in the area in 2002.

October 16, 1961 N.C. Caldwell State Highway Department witnesses shows he found a 1 1/4" axle shaft and raised it with a 5/8" bolt.

Wit: 14" Apple	N62°E	72.10'
13" Apple	N19°E	35.45'
T. Pole	N02°E	65.54'

Thomas Fabis P.S. # 31591 2001 found 1/2" iron rod inside monument box.

Wit: Road Sign	S40°E	87.59'
Tel. pole	North	65.35'
6" Pine	N10°E	93.46'
Guard Post	S35°W	53.95'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

J-8 Found 1/2" iron rod with P.S. cap #31591 in monument box.

9- Found and accepted a 1/2" rod with P.S. cap as set by Wayne T. Lewis.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-8 1/2" iron rod with P.S. cap #31591

Wit: Chiseled "X" in curb	S43°W	52.02'
Sign post	S45°E	88.93'
P. Pole	N02°E	65.51'
W. sign post	N65°E	24.60'

9- 1/2" rod with P.S. cap #41922

Wit: 5" Scotch Pine	S17°W	45.40'
5" Scotch Pine	S80°E	34.47'
5" Scotch Pine	N14°E	83.05'
Centerline of N-S trail	West	66'±
Carsonite post	North	1'±

Signed by: _____

Carl T. Kiiskila

Date: _____

3-22-04

Surveyor's Michigan License No.: _____

33981

