

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Alpena (County)	Located In	Corner Code #
1. Public Land Survey	T <u>31N</u> R <u>6E</u>	<u>M-4</u>
	T <u>31N</u> R <u>6E</u>	<u>M-3</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		

Register of Deeds Stamp & File Number

I, Carl T. Kiiskila, in a field survey on, April 30, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-4 G.L.O. Butler Ives 1855 Set quarter section post
 Wit: W. Pine 14 N43°W 66 links
 W. Pine 14 S18°E 76 links

M-3 G.L.O. Butler Ives 1855 Set post corner of sections 10, 11, 14 and 15.
 Wit: Hemlock 18 N60°W 23 links
 Hemlock 24 S22°E 31 links

Page 227, Alpena County Road Commission Board minutes dated April 8, 1916 indicate Joseph W. McNeil surveyed Herron Road in November of 1915 and Recorded the courses adopted in the April 8, 1916 minutes.

Page 227, Alpena County Road Commission Board minutes dated April 8, 1916 indicate Joseph W. McNeil surveyed Herron Road in November of 1915 and Recorded the courses adopted in the April 8, 1916 minutes.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

M-4 Re-established the East quarter corner of section 12 prorating to J.W. McNeil's November 1915 bearings and distances recorded in the April 1916 Alpena County Road Commission Board minutes.

M-3 Found a 1 1/2" pipe 16" below grade similar to other corners set by J.W. McNeil in Herron Road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 Set 5/8" X 32" rerod with P.S. cap #33981
 Wit: 5" Cedar N46°W 63.32'
 5" Maple N70°E 118.95'
 P.Pole S85°E 44.91'
 5" Tamarack S40°E 129.09'
 Carsonite Post East 50'±
 Centerline of Herron Road

M-3 Found 1 1/2" pipe raised with 5/8" X 32" rerod with P.S. cap #33981
 Wit: 8" Twin Maple S60°W 44.19'
 8" Maple Clump N72°W 46.93'
 16" Red Pine S32°E 166.71'
 1" Pipe N02°W 7.68'
 P.Pole nail w/ tag N60°E 62.67'
 Carsonite Post East 50'±
 Centerline of Herron Road

Signed by: _____

Carl T. Kiiskila

Date: _____

3-22-04

Surveyor's Michigan License No.: _____

33981

