

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Alpena (County)	Located In	Corner Code #
1. Public Land Survey	T <u>31N</u> R <u>6E</u>	<u>M-6</u>
	T <u>31N</u> R <u>6E</u>	<u>M-7</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on, May 8, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-6 G.L.O. John Hodgson 1855 set 1/4 section post
 Wit: Tamarack 16 N51°W 9 links
 Tamarack 18 S48°W 19 links

M-7 G.L.O. John Hodgson 1855 Set post corner 13 and 14
 Wit: Cedar 9 S66°W 8 links
 Cedar 7 N41°W 16 links

Page 227, Alpena County Road Commission Board minutes dated April 8, 1916 indicate Joseph W. McNeil surveyed Herron Road in November of 1915 and Recorded the courses adopted in the April 8, 1916 minutes.

Page 227, Alpena County Road Commission Board minutes dated April 8, 1916 indicate Joseph W. McNeil surveyed Herron Road in November of 1915 and Recorded the courses adopted in the April 8, 1916 minutes.

Liber 2. Page 412 December 2001, Gary W. St Charles P.S.# 27431 Set 1/2" iron rod over center of existing 1 1/2" pipe.

Wit: 7" Spruce N50°E 54.27'
 24" Spruce S82°E 77.77'
 Fence Cor. West 34.50'
 Power Pole S37°W 87.85'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

M-6 Found a 2" pipe 16" below grade fitting J.W. McNeil's distances.

M-7 Found 1/2" rerod with P.S. cap #27431

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 Found 2" iron pipe placed a 5/8" X 32" rerod with P.S. cap #33981 in the center.

Wit: P.Pole S85°E 57.32'
 5" Spruce S58°W 44.39'
 7" Twin Maple N64°W 43.34'
 7" Spruce S44°E 139.97'
 Carsonite post East 50±
 Center of Herron road east 3±

M-7 Found 1/2" rerod with P.S. cap #27431

Wit: Fence Post N89°W 34.46'
 Power Pole S32°W 87.77'
 24" Spruce S88°E 77.68'
 5" Spruce N53°E 54.20'

Signed by: _____

Carl T. Kiiskila

Date: _____

3-22-04

Surveyor's Michigan License No.: _____

33981

