

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alpena (County)

Located In: Corner Code #

Table with 3 columns: Item description, Township/Range, and Corner Code. Includes items like 'Public Land Survey' and 'Property Controlling in Section'.

JUN 17 10 58 AM '96

Kathy Mptash REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13, likely for recording section numbers.

I, Earl T. Lewis in a field survey on April 10, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: Butler Ives Used a Hemlock 14" for corner, no witnesses given.
1883: W. Mirre Used corner, set 4" square cedar stake from GLO witness. Left some brick, an iron ring, and stones at corner. No witnesses given.
1914: J. McNeil Used corner. No monumentation or witnesses given.
1958: G. Jerome & Co. Used corner. No monumentation or witnesses given.
1995: David Guthrie, P.S. Used corner. Found nail. Set 1/2" iron rod. Witnesses given: S 50' W 51.84' Utility Pole, N 42' W 72.24' Utility Pole, N 89' E 46.90' 6" Aspen, S 81' E 64.34' 6" Spruce

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found 1/2" rered w/cap #22435.

SURVEY & REMONUMENTATION

JUL 23 1996

COMMISSION

P.A. 345 ALPENA COUNTY PEER APPROVED 5/5/1996 [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on existing 1/2" rered in monument box.

Witnesses given:

- N 89' E 46.91' 6" Aspen (found tag)
S 81' E 64.36' 6" Spruce (found tag)
N 42' W 72.25' Utility Pole (found tag)
S 50' W 51.84' Utility Pole (found tag)



Signed by Earl T. Lewis

Date June 12, 1996

Surveyor's Michigan License No. 27452