

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUN 17 10 58 AM '96

Kathy Matash REGISTER OF DEEDS

For corners in Alpena (County)

Located In: Corner Code #

Table with 3 columns: Description (Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.), Located In (T, S), and Corner Code (#). Includes handwritten 'A12' in a circle.

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

Earl T. Lewis in a field survey on April 10, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: Butler Ives Set corner. Witnesses given: Cedar 20 N 75° W 21, Birch 7 S 37° W 11.
1891: Fred A. Rice Set corner. No witnesses given.
1914: J. McNeil Set corner. No witnesses given.
1969: J. L. Scott Used corner. Found 3/4" pipe. No witnesses given.
1977: Jerry L. Wilcox Found 1-1/2" pipe and recorded corner in Liber 1 of Corners, page 89. Witnesses given: N 80° W 47.50' 4" Elm, N 45° W 71.10' 6" Spruce, N 60° E 51.16' Corner Fence Post, S 35° W 88.15' 8" Pine
1987: David B. Guthrie Used corner. Found 1/2" iron rod. Witnesses given: N 30° W 76.00' Twin 6" Balsam, N 80° W 55.00' 6" Balsam, S 30° W 87.70' 8" Balsam

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found 1/2" rerod w/unidentifiable cap & found 3/4" pipe.

SURVEY & REMONUMENTATION

JUL 23 1996

COMMISSION

P.A. 345 ALPENA COUNTY PEER APPROVED 5/5/96 D.B. Guthrie

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on 1/2" rerod inside existing pipe in monument box.

- Witnesses given:
S 25° W 148.86' 20" Cedar
N 30° W 91.65' Power Pole
S 25° E 180.27' Power Pole
N 25° E 89.59' 6" Balsam



Signed by Earl T. Lewis

Date June 12, 1996

Surveyor's Michigan License No. 27452