

RECORDED
ALPENA COUNTY MI.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Alpena (County)

Located In:

Corner Code ##

- 1. Public Land Survey
 - T 31N R 07E A13
 - T 31N R 06E R13
 - T _____ R _____
 - T _____ R _____
- 2. Property Controlling in Section
 - S _____ T _____ R _____
 - S _____ T _____ R _____
- 3. Miscellaneous Property in Sec.
 - S _____ T _____ R _____
 - S _____ T _____ R _____

JUN 17 10 58 AM '96
Kathy G. Mptash
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

Earl T. Lewis, in a field survey on April 10, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: Lewis Glason Set corner. Witnesses given: Cedar 10 N 54° W 31', Spruce 24 N 67° E 17'
- 1891: Fred A. Rice Used corner. Found stake. No witnesses given.
- 1914: J. McNeil Used corner. Set 1-1/2" steel shaft over wood stake. No witnesses given.
- 1969: J. L. Scott Used corner. Found T-iron. No witnesses given.
- Unknown: Alpena Co. Road Com. Used corner. Found 1/2" rerod. Witnesses given:
N 20° E 42.42' 4" Poplar
S 42° E 47.75' Power Pole
N 12° W 59.33' 4" Poplar
- 1993: Earl T. Lewis Used corner. No monumentation or witnesses given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1996: Found 1/2" rerod.

P.A. 345 ALPENA COUNTY
PEER APPROVED 5/5/96

D. B. Ceter

Survey & Remonumentation

MAY 18 1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1996: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on existing 1/2" rerod 0.3' below surface.

Witnesses given:

- S 55° E 47.98' Power Pole
- S 15° E 122.50' 12" Aspen
- N 45° W 62.56' 5" Aspen
- S 75° E 104.04' Fence Post



Signed by Earl T. Lewis

Date June 12, 1996

Surveyor's Michigan License No. 27452