

SURVEY & REMONUMENTATION

1994 ALPENA County Remonumentation Corner

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
 ALPENA COUNTY, MI.
 LIBER 1 PAGE 310
 Oct 11 10 38 AM '94
Maury D. Johnston
 REGISTER OF DEEDS

For corners in

Alpena <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>31N</u> R <u>7E</u>	<u>E-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Daniel T. Kibbe, in a field survey on May 24, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1855: G.L.O. Re-survey by Butler Ives - set post & referenced: B. Ash 30 - S 55° W - 13 / Cedar 12 - N 13 E - 20.
 1961: Monument Witness Record by N.C. Caldwell - fnd. 3/4" iron bar at location described on old highway plans & referenced.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1994: Set 1/2" iron bar with 3" aluminum cap in monument box 16.8' South of centerline M-32.

This corner position was established from a 1961 MSHD witness and prorated measurements from 1963 MSHD Construction Plans. This location is accepted as a careful and faithful re-establishment of the position of the original corner.

P.A. 345 ALPENA COUNTY
 PEER APPROVED Sept. 8, 1994
Paul B. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 1994: Placed monument box with 1/2" iron rod and 3" aluminum cap stamped to identify the corner.
 Referenced:
 S 09° E - center of 12" Elm stump - 95.40'
 S 34° W - set nail in T. pole - 85.88'
 S 02° E - set nail in 18" Maple - 111.55'
 S 56° E - set nail in 9" Ash - 125.01'
 N 38° W - set nail in new power pole - 171.74'



Signed by *Daniel T. Kibbe*
 Surveyor's Michigan License No. 37278

Date August 3, 1994