

**SURVEY & REMONUMENTATION**

DEC 17 1994  
1994 Alpena County Remonumentation Corner

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alpena <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>31N</u> R <u>7E</u>	<u>H-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED  
ALPENA COUNTY MI.  
LIBER **1** PAGE **307**  
OCT 11 10 38 AM '94  
*Margaret A. Johnston*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Daniel T. Kibbe, in a field survey on June 9 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- 1855: G.L.O. Re-survey by Butler Ives - set post & referenced: Y. Pine 20 - N 84 E - 38 / Y. Pine 15 - S 34 W - 85.
  - 1892: County Survey by Wm. H. LeRoy - re-established old 1/4 corner, set cedar stake & referenced.
  - 1910: County Survey by Jos. W. McNeil - referenced.
  - 1930: County Survey by Wm. H. LeRoy - set 1"x36" iron pipe & referenced.
  - 195 : Survey by Scott Engr. Co. - set "T" iron & referenced.
  - 1961: Monument Witness Record by N.C. Caldwell - fnd "T" iron & referenced.
  - 1963: MSHD Construction Plans - referenced "T" iron.
  - 1964: Survey by James Scott - Airway Acres Plat
  - 1968: MSHD - Re-witnessed 1/2" iron rod.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1976: Survey by David Guthrie - found mon. box.
  - 1992: Survey by Earl Lewis - found mon. box & referenced.

B.  
1994: Found 1/2" iron bar in monument box.

This corner position is compatible with local surveys and agrees with MDOT records. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY  
DEER APPROVED Sept. 8, 1994  
*Del B. Carter*

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- 1994: Placed 3" aluminum cap stamped to identify the corner over existing 1/2" iron rod in monument box.
- Referenced:
- N 38° E - center 5" steel fence post cut off flush with ground - 89.65'
  - N 37° W - center 5" steel fence post cut off flush with ground - 93.84'
  - S 65° E - center base of fence post at NE end clear vision fence - 201.85'
  - S 70° W - center base of fence post at NW end clear vision fence - 202.85'

Signed by *Daniel T. Kibbe* Date August 3, 1994  
Surveyor's Michigan License No. 37278

