

SURVEY & REMONUMENTATION

1994 Alpena County Remonumentation Corner
DEC 07 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
ALPENA COUNTY MI
LIBER 1 PAGE 305
OCT 11 10 38 AM '94
W. A. Johnston
REGISTER OF DEEDS

For corners in

Alpena <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>31N</u> R <u>7E</u>	<u>J-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Daniel T. Kibbe, in a field survey on June 9, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: G.L.O. Re-survey by Butler Ives - set post and referenced: Spruce 6 - S 30 E - 20 / Spruce 4 - N 16 W - 12
- 1891: County Survey by Wm. H. LeRoy - No original corner found. Set corner and referenced: Cedar Stake 2 - South - 9
- 1961: Monument Witness Record by N.C. Caldwell - set 1/2" bar from witnesses on file at Scott Engr. Co. and referenced.
- 1963: MSHD Construction Plans - referenced 1/2" iron bar.
- 1977: Survey by Duane MacNeill
- 1984: Survey by Duane MacNeill - found mon. box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1994: Found 1/2" iron bar in monument box.

This corner position is compatible with county and local surveys and agrees with MDOT records. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY
PEER APPROVED Sept. 8, 1994
D. B. Carter

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1994: Placed 3" aluminum cap stamped to identify the corner over existing 1/2" iron rod in monument box.
Referenced:
N 31° E - fnd. MSHD nail & tag in 20" blazed Jack Pine - 81.85'
S 27° W - fnd. MSHD nail & tag in power pole - 72.56'
N 15° W - set nail in 10" Jack Pine - 70.12'
S 03° E - set nail in 10" Cedar - 84.55'



Signed by Daniel T. Kibbe
Surveyor's Michigan License No. 37278

Date August 3, 1994