

MAY 18 1997

1996 ALPENA COUNTY REMONUMENTATION CORNER

LIBER 2 PAGE 47

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alpena (County)

Located In:

Corner Code #

1. Public Land Survey

T 31N R 8E

I-2, (E1, 3) ✓

T R

Alpena Twp.

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Section

S T R

4. Lot No. , Recorded Plat

5. Private Claims

RECORDED ALPENA COUNTY MI.

JUL 22 11 07 AM '96

Handwritten signature

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column I and row 2.

I, Thomas L. Fabis, in a field survey on May 9, 1996

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: G.L.O. Resurvey by Josiah Knauer - Set post & referenced: (Hemlock 14 - N87W - 5 1/2 lks., Cedar 16 - N80E - 25 lks.)
1977: Survey (Liber 1 Page 571) by Delmer Porter and L.C.R.C. (Liber 1 Page 92) by Ron Bischer - Found 5/8" Rod and witnessed.
1978: Survey (Liber 1 Page 591) by Delmer Porter - Found 5/8" Rod & previous witnesses.
1978: Survey (Liber 1 Page 738) by David Guthrie of R.S.Scott Assoc. - Existing 1/2" iron rod and witnesses same as Porter.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found 5/8" Rod and two witnesses.

The position of this corner is compatible with the recorded surveys mentioned above and is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY PEER APPROVED 5/16/96 [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Removed 5/8" Rod and set 1/2" iron rod capped with 3" dia. aluminum cap, stamped to identify the corner.

Reestablished witnesses are:

- Existing shiner tag in Anchor Pole - Due East - 25.59'
Existing shiner tag in Tele. Pole - Due West - 31.36'
Set tag #31591 in Tele. Pole - S35W - 76.75'
Set tag #31591 in 3" Spruce - S25E - 52.81'



Signed by Thomas L. Fabis

Date July 17, 1996

Surveyor's Michigan License No. 31591