

ALPENA

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 31 N. R. 9 W.	G 11, H 11
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	H-I 11 (M.C.)
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	H-I 9 (M.C.)
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, **Gary C. Bilow** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on **December 7, 1979**, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G 11 Cedar stake OBT, N 44° W, 2½ links	H 11 3" squared cedar stake 8" Birch, S 24° E, 19 links	H-I 11 (Meander Corner) post 5" Cedar stub (ONBT), S 69° W, 7 links 9" dead Cedar, N 48° W, 10 links 7" Cedar, S 24° W, 8½ links
H-I 9 (Meander Corner) post 7" dead Cedar, N 35° W, 16 links 7" Tamarack, S 12° E, 16 links		

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G 11 found squared post with three notches on east edge, witness lost
H 11 found squared post scribed ¼ S, does not agree with witness
H-I 11 found squared post at approximate GLO distance from ¼ corner, witness lost
H-I 9 found 1" pipe at approximate GLO distance from ¼ corner, witness lost

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G 11 replaced post with 1" pipe with aluminum cap 1 ft. E. of 2-wire fence; N 10° W, 13.6 ft, face of blaze twin 7" Birch; S 45° W, 4.5 ft, face of blaze 4" Fir; N 60° E, 16.0 ft, face of blaze 10" Fir; SSE, 2.5 ft, steel fence post	H 11 replaced post with 1" pipe with aluminum cap N 2° E, 17.6 ft, face of blaze 9" Cedar N 80° W, 17.9 ft, face of blaze 10" Cedar N 80° E, 9.6 ft, face of blaze 4" Cedar set old post as witness, 1 ft. S.
H-I 11 (Meander Corner) replaced post with 1" pipe with aluminum cap N 82° W, 69.9 ft, face of blaze 8" Cedar N 32° W, 45.4 ft, face of blaze 7" Cedar N 7° E, 40.6 ft, face of blaze 7" Cedar set old post as witness, 1 ft. SE	H-I 9 (Meander Corner) left 1" pipe as corner; SSW, 11.6 ft, 4" Fir; W, 19.8 ft, 10" Cedar; 19 ft. E. of toe of beach ridge; 0.5 ft. W. of wood witness post; 40 ft. W of edge of Lake

SIGNED BY: *[Signature]*
SURVEYOR'S MICHIGAN REGISTRATION NO. 26453

DATE: *[Date]* /Huron

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR

DATE _____

(S.E.A.)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____