

SURVEY & REMONUMENTATION 994 ALPENA COUNTY REMONUMENTATION CORNER

007638

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alpena **APR 06 1995**

RECORDED ALPENA COUNTY MI.

Located In: _____ Corner Code # _____

1. Public Land Survey T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S 18 T 31N R 9E _____
 S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LIBER **Dec 29** **1** PAGE **347**
2 20 PM '94

Wm. A. Johnston
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Duane R. MacNeill in a field survey on May 12, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7	●											
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not set by Original Government Surveyor (Fell in Bay)

1958 - George Jerome & Company Surveyors show a position for this corner on their Plat Map, but no identification of corner provided.

No Witnesses Supplied

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1976 - D.R. MacNeill & Associates conducted a survey in Section 18 and used the George Jerome & Co. information and set p.k nail.

No Witnesses Supplied

P.A. 345 ALPENA COUNTY
PEER APPROVED 12-27-94
D. B. Utter

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Remonumentation Crew set 1/2" re-rod with an Alpena County Aluminum Remonumentation Cap, appropriately stamped, was secured to 1/2" re-rod at 6" below surface of Roadway and about 2 feet South of Centerline. This corner was re-established using the George Jerome & Company information and is a property controlling corner.
 (Monument box is provided)

Witnesses:

S80°E 87.25 6" Poplar
 N45°E 33.02 6" Poplar
 N75°W 90.80 Power Pole
 S70°W 81.30 5" Poplar

Signed by Duane R. MacNeill Date 12/28/94
 Surveyor's Michigan License No. 19237

