

**SURVEY & REMONUMENTATION**

**1994 ALPENA COUNTY REMONUMENTATION CORNER**

APR 06 1995

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

007637

For corners in  
 Alpena **COMMISSION**  
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>31N</u> R <u>9E</u>	<u>C-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

RECORDED  
 ALPENA COUNTY MI.  
 LIBER 1 PAGE 346  
 DEC 29 2 20 PM '94  
*Myra A. Johnson*  
**REGISTER OF DEEDS**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Duane R. MacNeill, in a field survey on May 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 - Cedar Post set by Josiah Knaner, D.S.

1925 - William H. Leroy found evidence of original corner and set 4" steel pipe.

Witnesses:

No Witnesses Supplied

Cedar 6" S32°E 4  
 Cedar 7" N36°W 7½

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1958 - George Jerome & Company was into corner but provided no identification.

1976 - D.R. MacNeill & Assoc. found concrete monument.

1984 - Alpena County Road Commission Surveyor finds concrete monument and after Road Construction complete raised with 1/2" re-rod.

No Witnesses Supplied

Witnesses:

N10°W 57.77 6" Cedar  
 S30°E 31.06 T.P.  
 S70°W 62.53 8" Cedar

Witnesses:

N10°W 57.80 8" Cedar  
 S50°W 62.59 8" Cedar  
 S15°E 31.07 Tel. Pole

**P.A. 345 ALPENA COUNTY**  
**PEER APPROVED** 12-27-94  
*Val B. Litch*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 Remonumentation Crew found 1/2" re-rod 6" below and approximately centered on Roadway surface. An Alpena County Aluminum Remonumentation cap, appropriately stamped, was secured to the existing 1/2" re-rod.

Witnesses:

N25°E 42.45 T.P.  
 N10°W 57.88 8" Cedar  
 S60°W 62.60 8" Cedar  
 S40°E 108.65 6" Cedar

Signed by *Duane R. MacNeill* Date 12/28/94  
 Surveyor's Michigan NO. 19237  
