

REMONUMENTATION

1994 ALPENA COUNTY REMONUMENTATION CORNER

007636

APR 06 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ALPENA COMMISSION  
(County)

Located In: Corner Code #

- 1. Public Land Survey T 31N R 9E D-7
- 2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

RECORDED  
ALPENA COUNTY MI.

LIPER 1 PAGE 345  
DEC 29 2 20 PM '94

*Wm. A. Johnston*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Duane R. MacNeill, in a field survey on May 12, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 16 | 17 | 18 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 - Cedar Post set by Josiah Knaner.      1925 - William H. Leroy found evidence of original corner and set cedar stake in rock pile.

Witnesses: Cedar 5" S39°E 17" Tam. 6" N40°W 5 1/2"      No Witnesses Supplied

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1976 - D.R. MacNeill & Assoc. found 3/4" x 2" bar stock.      1984 - Alpena County Road Commission Surveyor finds 3/4" x 2" bar stock, after Road Construction complete, raised with 1/2" re-rod.      1988 - R.S. Scott & Associates find 1/2" re-rod.

Witnesses: S55°E 60.94 12" R. Pine S50°W 89.04 17" Pine Due North 31.93 P.P.      Witnesses: S55°E 60.95 12" R. Pine S50°W 89.04 17" Pine      Witnesses: S70°W 89.00 16" R. Pi S40°E 60.85 12" W. Pi

PA. 345 ALPENA COUNTY  
PEER APPROVED 12-15-94  
*D. B. Lutz*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 Remonumentation Crew found 1/2" re-rod 6" below and approximately centered on Roadway surface. An Alpena County Remonumentation Cap, appropriately stamped, was secured to the existing 1/2" re-rod.

Witnesses: S45°W 79.01 8" Spruce S60°W 89.00 17" R. Pine S40°E 60.94 12" W. Pine Due North 31.93 P.P.

Signed by Duane R. MacNeill Date 12/20/94  
Surveyor's Michigan License No. 19231925

