

SURVEY & REMONUMENTATION

1994 ALPENA COUNTY REMONUMENTATION CORNER

007635

APR 06 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alpena **COMMISSION**
(County)

1. Public Land Survey	T <u>31N</u> R <u>9E</u>	<u>E-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED
ALPENA COUNTY MI.

LIPER **1** PAGE **344**
DEC 29 2 20 PM '94

Myriam A. Johnston
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Duane R. MacNeill, in a field survey on May 12, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 - Cedar Post set by Josiah Kraner.

1925 - William H. Leroy finds 6" x 8" Square cut stone.

Witnesses

Cedar 6" S48°W 21
Cedar 7" N29°E 7

Witnesses

Cedar 7" S48°W 21 O.N.B.T.
Cedar 9" N29°E 7 O.N.B.T.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1976 - D.R. MacNeill & Associates find 6"x 8" stone with 1" pipe.

1984 - Alpena County Road Commission finds 6"x 8" stone with 1" pipe, after Road Construction completed, raised with 1/2" re-rod.

1980's and 1990's - various Surveyors into this corner.

No Witnesses Supplied

Witnesses:

N20°E 40.50 6" Tamarack
N75°W 65.02 Wood Post
South 34.17 P.P.

P.A. 345 ALPENA COUNTY
PEER APPROVED 12-15-94
D. R. Coker

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 Remonumentation Crew found 1/2" re-rod 6" below and approximately centered on Roadway surface. An Alpena County Aluminum Remonumentation cap, appropriately stamped, was secured to the existing 1/2" re-rod.

Witnesses:

N25°E 40.44 6" Spruce
N45°W 69.56 6" Spruce
Due South 34.17 P.P.
S40°W 54.61 3" Pipe in Concrete

Signed by *Duane R. MacNeill* Date 12/28/94
Surveyor's Michigan License No. 10237

