

**SURVEY & REMONUMENTATION**

APR 06 1995

1994 ALPENA COUNTY REMONUMENTATION CORNER

007634

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alpena

(County)

Located In:

Corner Code #

- |                                       |   |            |   |           |            |
|---------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey                 | T | <u>31N</u> | R | <u>9E</u> | <u>F-7</u> |
|                                       | T | _____      | R | _____     | _____      |
|                                       | T | _____      | R | _____     | _____      |
|                                       | T | _____      | R | _____     | _____      |
| 2. Property Controlling in Section    | S | _____      | T | _____     | _____      |
|                                       | S | _____      | T | _____     | _____      |
| 3. Miscellaneous Property in Sec.     | S | _____      | T | _____     | _____      |
|                                       | S | _____      | T | _____     | _____      |
| 4. Lot No. _____, Recorded Plat _____ |   |            |   |           |            |
| 5. Private Claims _____               |   |            |   |           |            |

RECORDED  
ALPENA COUNTY MI.  
LIBER 1 PAGE 343  
DEC 29 2 20 PM '94  
*Myriam A. Johnston*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Duane R. MacNeill, in a field survey on May 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1856 - Cedar Post Set by Josiah Knaner, D.S.

Witnesses:

Cedar 7" S27°W 16  
Cedar 7" N28½W 12

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1976 - D.R. MacNeill & Associates find 1" threaded rod. (origin unknown)

No Witnesses Supplied

P.A. 345 ALPENA COUNTY  
PEER APPROVED 12-11-94  
*Paul B. Lester*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 Remonumentation Crew found 1" steel pin 6" below and approximately centered on Roadway surface. An Alpena County Aluminum Remonumentation cap, appropriately stamped, was secured to the existing 1" steel pin.

Witnesses:

S25°E 35.29 P.P.  
N02°W 35.59 Fence Post  
N30°W 58.55 4" Cedar  
S30°W 53.21 5" Spruce

Signed by

*Duane R. MacNeill*  
DUANE R. MAC NEILL  
LAND SURVEYOR  
NO. 11237  
19237  
REGISTERED LAND SURVEYOR

Date

12/28/94

Surveyor's Michigan License