

SURVEY & REMONUMENTATION

APR 06 1995

1994 ALPENA COUNTY REMONUMENTATION CORNER

007632

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
ALPENA COUNTY MI.

For corners in

Alpena
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey | T | <u>31N</u> | R | <u>9E</u> | <u>G-6</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER 1 PAGE 341-
DEC 29 2 20 PM '94

Myriam A. Johnston
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Duane R. MacNeill, in a field survey on May 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 - Cedar Post set by Josiah Knaner, D.S.

1912 - Joseph McNeil locates corner and sets cedar stake.

Witnesses

Balsam 6" N83°W 3
Y. Birch 10" S58°E 16

No Witnesses Supplied

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1981 - D.R. MacNeill & Associates finds 1/4" x 1" bar stock.

Witnesses

S15°W 43.81 5" Birch
S45°E 50.03 P.P.
Due East 34.69 Fence Post.

P.A. 345 ALPENA COUNTY - 94
PEER APPROVED 12-15-94
D. B. Luter

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 Remonumentation Crew found 1/4" x 1" bar stock 5" below and approximately centered on Roadway surface. An Alpena County Aluminum Remonumentation Cap was placed on 1/2" re-rod next to 1/4" x 1" bar stock.

Witnesses:

Due East 34.72 Fence Post
S45°E 50.08 P.P.
Due West 20.60 4" Cedar
S45°W 45.39 5" Cedar

Signed by *Duane R. MacNeill*
Surveyor's Michigan License No. 19237

Date 12/28/94

